



'Dead' Hedge
Project to be undertaken by volunteers

Cobbled sett paving.
To be cleared of ingrowing vegetation and re-pointed where necessary. (75m²)

Persevere ship mural.
To be cleaned & brought back to life

Woodland bulb planting
With pockets of woodland ground cover species. (105m²)

Successional bulb planting
(35m²)

Community Planting bed
130m²

Successional bulb planting
(65m²)

First tree to be removed

Crown lifting of whole lime tree avenue - by CEC Forestry.
Stump has potential to become carving project.

Entrance cobbled setts.
To be cleared of ingrowing vegetation and re-pointed where necessary.


Signage
New noticeboard, threshold sign, and Edinburgh Nature Network sign located around the entrance of the park.

Bin moved to here.
Could be upgraded to 250L bin

NJS Key



Existing trees
Planned works to be carried out by CEC forestry



Successional Bulb Planting
Area = 345m²
Narcissus @ 25/m² / Crocus @ 75/m² / Fritillary @ 75/m²



Woodland Bulb Planting
Area = 420m²
Bluebells @ 75/m² / Snowdrops @ 75/m² / Wild Garlic @ 50/m²



Ornamental Planting Bed
Planted with mixed native species as per the Atkins species lists on drawing 5220321-ATK-LL-NJS-SC-L-101. Area = 280m²



Existing Vegetation
Thinned out and replanted with native ornamental planting. Allow for planting about 50% of area with larger stock. Area = 380m²



Urban Pollinator Mix
Area = 200m²



Existing Amenity Grass



Hedgerow
Length = 17.5m



Log Edging
15cm - 30cm diameter logs to be supplied from onsite and local arboricultural works. Total length of logs needed = 200m



Existing Benches



Opportunities for New Benches

Stair Railing
To be repainted

Urban pollinator mix
(200m²)

Potential for central gathering/seating space

Community Planting bed
(10m²)

Path clearance work
Needed for ALL paths in the park

Exsting Wall & Railing
Railing to be repainted

Existing Vegetation
Thinned back and in-filled with woodland herbaceous/shrubs. (85m²)

New log edging.
100-150mm edge height to these planting beds

Woodland bulb planting
With pockets of woodland ground cover species. (315m²)

Stair Railing
To be repainted

Holly/Hawthorn Hedgerow
(Length = 17.5m)

Hard surface area
Covered in encroaching vegetation/grass. Scrape back grass and make good surface. (115m²)

Retained Open Amenity Grass

Retained Open Amenity Grass

Threshold Sign
Affixed to railing

Bin moved to entrance.
Could be upgraded to 250L bin

Rewilded areas.
Larger deadwood left and half buried. Bark mulch layer with woodland planting. Information board added. (110m²)



Existing vegetation
Thinned back and in-filled with woodland herbaceous/shrubs. (160m²)



New log edging to formalise beds.



Edinburgh & Lothians Greenspace Trust
Swantson Steading, 109 / 11 Swantson Road
Edinburgh EH10 7DS
0131 445 4025

Title
Linking Leith Parks
Nature Restoration Fund
North Junction Street Park
Landscape Proposals

Rev No	Scale
Rev 05	1:250 @ A3
Date	Drawn by
13.12.24	A.Fisher
Drawing Number	Date of first issue
917_NJSP	12.10.24